


ROBOTICS

Diesel Engine Assembly Line



Facts	
Industry	Automotive OEM
Product	Diesel Engines
Installation Date	November 2005
	Diesel Engine assembly line is based on ABB standard modular concept. This line consists of three conveyor systems, one for short block assembly, one for piston sub assembly and one for cylinder head sub assembly. The assembly lines are a mix between manual, semi automatic and automatic stations, between some of the assembly stations is a buffer station placed.
Description	Currently assembles 13 liters (6 cylinder) engines with weekly production reaching 1000 units with two shift operation.
Equipment	21 Automatic stations 23 Manual stations 4 Semi-auto stations 15 robots ABB leakage test for injector assembly ABB automatic assembly of piston rings
	High quality assembly processes to assure product quality and production Cost effective solution High flexibility Easy and low cost startup of new variants
Customer Benefits	ABB service close to customer





Facts	
Technical Data	Capacity: 50,000/year (2-shift production)
	Cycle time: 183 seconds
	Leakage test station of cylinder head.
	Robot assembly of cylinder liner gasket
Unique Elements:	Automatic adjustment of valve clearance.
Customer Provided Equipment	N/A
	Concept design
	Concept approval
	Engineering (Detail design)
	Project management
	Manufacturing
	Installation
Project/Steps to Implementation	Training
Project Responsibility:	Powertrain
Video/Photos/Reference:	Can be supplied by ABB